





LEGEND




Proposed specimen marker tree
Refer to erz/19 10/P03 for species and spec
Refer to detail erz/19 10/DP04



Proposed street tree
Refer to erz/19 10/P03 for species and spec
Refer to detail erz/19 10/DP04



Existing tree retained



Existing grass retained




Area to be re-turfed
Refer to erz/19 10/P03 & DP01




Existing shrub planting retained




Existing hedge planting retained



Proposed hedge planting
Refer to erz/19 10/P03 for species
Refer to detail erz/19 10/DP03



Proposed shrub/herbaceous planting
Refer to erz/19 10/P03 for species
Refer to detail erz/19 10/DP03



Precast concrete setts
300x100x100mm units (loose)
Mix of light and mid grey, herringbone
with soldier trim
Refer to erz/19 10/P08




Fresh bound gravel
Colour - Pearl/gray/white mix
6mm aggregate
Refer to detail erz/19 10/DP03




Loose gravel
Aggregate Silver grey granite, with gravel
containment system
Refer to detail erz/19 10/DP03



New asphalt to footways
Refer to detail erz/19 10/DP03




Pre-cast concrete flat top edging, 50mm
wide, S&F finish
Refer to erz/19 10/P06



Pre-cast concrete kerbs, inc drop kerbs
and radii units
Refer to detail erz/19 10/DP03



Aluminium edging



Existing railing
Steel railing, stripped and re-painted




Proposed length of corten railing
Corten bespoke railing, laser cut infill bars
with corten frame and Oak top, 1.2m tall
Refer to detail erz/19 10/DP01




Steel handrail with Oak top
Refer to detail erz/19 10/DP03




Site boundary
Offset to avoid obscuring proposals




Low walls
Scottish Whinstone, coursed random
rubble with dressed copes and trim
Refer to detail erz/19 10/DP02



Proposed benches
Timber slats, steel frame
Refer to detail erz/19 10/DP04



Proposed picnic benches
Timber slats, steel frame
Refer to detail erz/19 10/DP03



Bollards
Refer to detail erz/19 10/DP02



Wayfinding vertical markers
Refer to detail erz/19 10/DP06 & DP07



Cycle stands
Refer to detail erz/19 10/DP01



Dropped curb location
Refer to erz/19 10/P06

- 2no. Speed reduction camera/signs, location tbc
- Works adjacent to community hall not part of contract
- Vehicle access to rear of hall remains, not part of works
- Reverse in / out flow to car park, allowance for signage and lining
- Existing ramp retained, not part of works
- Bays re-lined to free up space
37no. bays & 3no. disabled bays
- Existing memorial retained
- Existing slipway, allowance for localised repairs
- Relocated bus pull in with raised bus boarder kerbs
- Relocated bus shelter
- Relocated recycling bins
- Relocated map board

